



DID YOU KNOW?

Fyffe House, Built in NZ in 1860, by people in the whaling business, rests on whale bone piles.



The Marquette Interchange, Milwaukee, WI

By Pat Hannigan, GRL Engineers and Van Komurka, WKG²

The confluence of Interstate Highways I-94, I-43 and I-794 immediately southwest of downtown Milwaukee, Wisconsin comprises the Marquette Interchange. The original interchange opened in 1968 and was supported on low-capacity H-pile and pipe pile foundations. By 2000, the interchange handled over 300,000 vehicles per day, or roughly twice the intended capacity. The Wisconsin Department of Transportation (WisDOT) had the interchange completely reconstructed from 2004 through 2008 to meet the increased traffic demands and to improve traffic safety.

The reconstructed five-level interchange occupies the same general footprint as the original one, and is supported by more than 120 km (77 mi) of 32, 36 and 41 cm (12.75, 14 and 16 in) outside diameter closed-end pipe piles. These pile sections were installed at a cost of 19.3 million dollars to support maximum design loads of 1334, 1779 and 2224 kN (150, 200, and 250 tons), respectively. Maximum design loads of this magnitude had never been previously used by WisDOT.

Early in the design process, Milwaukee Transportation Partners LLC (MTP), the designer, determined that high-capacity pile foundations were the most cost-effective foundation solution for this project. High-capacity pipe pile



Marquette Interchange, completed project.
Photo by WisDOT Marquette Interchange Project Team

foundations were chosen over a lower capacity pile foundation design because of the reduced substructure size, the reduced utility impact, and the significant cost savings provided. The use of higher capacity piles also meant that there were fewer piles to drive, which contributed to maintaining a very aggressive project schedule.

The interchange covers a large area with highly variable soil conditions and high soil set-up potential. On average, a nearly six-fold increase in shaft resistance occurs between the end of initial driving and one month later. To achieve cost-effective foundation construction, the soil set-up was quantified and incorporated into the production pile installation criteria. Wagner Komurka Geotechnical Group (WKG²), working with GRL Engineers, used the results from an extensive 2003 design-stage test program during which 88 indicator piles were driven at select locations throughout the interchange footprint. Those indicator piles were dynamically tested by GRL during initial driving and during multiple restrike events to quantify



GRL's APPLE system was used on re-strike Dynamic Load Tests.

both the time rate and magnitude of soil set-up. GRL used a Pile Driving Analyzer[®] (PDA) for the dynamic tests and performed CAPWAP[®] analyses on the collected data. GRL's 15 ton APPLE system was used to effectively perform the long-term restrike tests on the indicator piles and to mobilize the large soil resistances. The design stage test program also included six axial compression load tests and six lateral load tests so MTP could optimize foundation selection.

During production pile installation, GRL Engineers performed dynamic pile monitoring with the PDA on the initial production piles driven at each substructure location. These production piles were also dynamically tested during restrike after a period of one to three days. GRL once again performed CAPWAP analyses on the collected data from end of drive and restrike. Approximately 10% of the production piles were dynamically tested in this manner. WKG² compared the long-term soil set-up information quantified in the design-stage test program with the short-term soil set-up information gathered from the production piles, and then established driving criteria for the remaining piles at each substructure location. WKG² used depth-variable driving criteria that considered the reduced end of driving capacity required as pile penetration depth increased, and the additional capacity achieved with penetration depth through soil set-up. Incorporating set-up and depth variable criteria into the pile installation criteria meant driving the piles as short as possible. Individual driving criteria was thus developed for each of the 254 substructure locations that comprised the Marquette Interchange.

The contractor, Marquette Constructors LLC, routinely operated 6 pile driving rigs at the same time and at one time had as many as 10 pile driving rigs operating concurrently. Single acting diesel hammers with rated energies of 54,500 to 223,200 Joules (40,200 to 164,600 ft-lbs) were used to install the over 5000 production piles. These hammers were significantly larger than those typically used on other WisDOT projects. The use of the larger hammers resulted in improved production installation rates.

The dynamic pile testing program contributed to an efficient foundation installation during the rebuilding of the congested interchange. The project was completed in August 2008 ahead of schedule and below the estimated cost of 810 million dollars.

2009 Calendar of Events Highlights

For a complete listing visit www.pile.com/events

May 11-14, Phoenix, AZ: 34th Annual Geotechnical Engineers Conference. Sponsored by Arizona DOT & FHWA. **Visit the PDI/GRL exhibit booth.** Info: NWetz@azdot.gov.

May 31-June 5, Honolulu, HI: Conference on Ocean, Offshore and Arctic Engineering (OMAE 2009). Sponsored by American Society of Mechanical Engineers (ASME), International Petroleum Technology Institute and University of Hawaii. **Frank Rausche will present.** www.asmeconferences.org/OMAE09/

June 4-6, San Francisco, CA: Super Pile 09. Sponsored by Deep Foundations Institute. **George Piscalko will present. Visit the PDI exhibit booth.** www.dfi.org

June 14-20, Utah State University, UT: Professor's Driven Pile Institute. Sponsored by PDCA. **Frank Rausche and Pat Hannigan will present.** www.piledrivers.org/profdrivenpile.php

July 1-3, Lisbon, Portugal: 1° Congresso de Segurança e Conservação de Pontes - Bridge Safety and Maintenance (in Portuguese). Sponsored by ASCP. www.dec.fct.unl.pt/~ascp/index.htm. **Visit the booth of PDI representative Tecnilab.**

July 20-24, Porto, Portugal: 3rd International Conference on Integrity, Reliability & Failure. Sponsored by School of Engineering, University of Porto and University of Toronto. **Visit the booth of PDI representative Tecnilab.**

August 31-September 6, Maputo, Mozambique: International Fair of Maputo. Sponsored by SOGEX, S.a.r.l. Info: sogex@sogex.com. **Visit the booth of PDI representative Tecnilab.**

September 14-16, Stockholm, Sweden: European Offshore Wind Energy Conference. Sponsored by European Wind Energy Association. www.eow2009.info **Visit the booth of PDI representative G-Octopus.**

September 23-25 Philadelphia, PA: High Strain Dynamic Pile Testing Exam, preceded by Preparatory Workshop. Sponsored by PDCA and Foundation QA. Dr. Julian Seidel will present. www.foundationqa.com

October 21-23, Kansas City, MO: DFI 34th Annual Conference on Deep Foundations. Sponsored by Deep Foundations Institute. **Visit the PDI exhibit booth.** www.dfi.org

November 2-4, Hershey, PA: 24th Central Pennsylvania Geotechnical Conference. Sponsored by PENNDOT and Central PA Section of ASCE. **Visit the PDI/GRL exhibit booth.** www.stegmanengineering.com/asce-pa2009.htm

November 19, San Francisco, CA: Design and Installation of Cost Effective Piles (DICEP). Sponsored by PDCA. www.piledrivers.org.

FRANK RAUSCHE AWARDED PRESTIGIOUS GBE AWARD

Frank Rausche, PhD, PE, has been awarded the 2009 G. Brooks Earnest Technical Lecture Award by the Cleveland Section of the American Society of Civil Engineers (ASCE). The award is presented yearly to an outstanding individual of prominence in the field of Civil Engineering, who delivers a Technical Lecture. Previous recipients include Ralph Peck, T. William Lambe, Elio D'Appolonia, Gerald A. Leonards, George Goble and many other distinguished engineers. Dr. Rausche will deliver the Technical Lecture in Cleveland this Fall.

CALL FOR PAPERS: ASCE GEOTECHNICAL SPECIAL PUBLICATION HONORING BENGT H. FELLENIUS

The ASCE Geo-Institute is soliciting abstracts for technical papers to be considered for inclusion in the Geotechnical Special Publication (GSP) entitled *Role of Full-Scale Testing in Foundation Design* honoring Prof. Bengt H. Fellenius, Dr. Tech., P.Eng., M.ASCE. Technical papers covering all aspects of foundation testing, design, and construction practices will be considered. Papers documenting case histories are particularly welcome. Deadline for abstract submission is September 30, 2009. Finished manuscript is expected in late 2010. Please e-mail abstracts (up to 300 words) to Mohamad H. Hussein at: MHGRL@pile.com.

INTERNATIONAL FOUNDATION CONGRESS AND EQUIPMENT EXPO '09

The International Foundation Congress and Equipment Expo '09 in Orlando, Florida, was attended by over 2700 individuals from around the world. Mohamad Hussein chaired the successful event, where 240 papers were presented and twelve panel discussion sessions held. The exhibitors – indoors and outdoors – totaled 150. The Geo-Institute of ASCE, ADSC and PDCA all held their annual meetings at the event. Garland Likins was awarded the PDCA Presidential Award for Distinguished Service during IFCEE.

FULL LINE OF PDA SENSORS NOW AVAILABLE WITH WIRELESS TRANSMISSION

Pile Dynamics has expanded its line of wireless Pile Driving Analyzer® (PDA) sensors to include Piezoelectric (PE) accelerometers. While Piezoresistive (PR) Accelerometers have been available with wireless transmission option for many months, and are suitable for any testing application, some PDA testers prefer using PE accelerometers when testing concrete piles. Wireless sensors avoid the use of cables; data is transmitted to a PDA model PAX via a dedicated radio transmitter. The wireless option is only available with the model PAX.

PDI customer Aksan Kawanda, from Geotech Engineering in Jakarta, says that the engineers in Indonesia call the wireless option "the future thing", adding "It is very, very helpful and amazing". Geotech used wireless sensors on a near-shore jetty, part of a Coal Fired Power Plant (300-400MW) located at Indramayu, in West Java, Indonesia. Dynamic tests with the PDA model PAX-8 were conducted on a test pile, both at end of driving and at a 10 days restrrike. During production, several piles were monitored with the PDA model PAX-4 using wireless sensors, keeping the PDA safe and dry on shore. See photo above.



Red circle: Wireless sensors attached to pile;
Blue circle: Engineers conducting the test with the PDA model PAX

PDI ADDS REPRESENTATIVE IN EGYPT

PDI now has a presence in Egypt, as it welcomes Market Leaders to its network of worldwide representatives. Visit www.pile.com/pdi/agents to locate one in your part of the world.

Visit us at WWW.PILE.COM



GRL Engineers, Inc.
Main Office: 4535 Renaissance Parkway
Cleveland, Ohio 44128 USA
E-mail: info@pile.com

Phone: +1-216-831-6131
Fax: +1-216-831-0916



Pile Dynamics, Inc.
4535 Renaissance Parkway
Cleveland, Ohio 44128 USA
E-mail: info@pile.com
Phone: +1-216-831-6131
Fax: +1-216-831-0916